


BRUHAT BANGALORE MAHANAGAR PALIKE**Project Division, Yelahanka Zone****SCHEDULE - B****BBMP/2019-20/OW/WORK_INDENT36085****Improvements to Park beside to Ganesha Temple Sahakara Nagara in Ward no. 08**


SNo	Quantity	Item Name	Unit	Rates quoted by Sri.P KRISHNA	
				In figures	In words
1	7.06	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	226.04	Rupees Two Hundred Twenty Six And Paise Four Only
2	32.90	KSRRB M300-Construction of Embankment with Material Gravel/Murum KSRRB M300-53. Construction of embankment with approved material Gravel /Murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murum, watering charges & compaction by vibratory roller to 95% of proctors density.	Cum	361.00	Rupees Three Hundred Sixty One Only
3	54.09	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5678.40	Rupees Five Thousand Six Hundred Seventy Eight And Paise Forty Only
4	149.44	KSRB 4-1.5 : Providing and laying in position plain cement concrete of Mix M20 with OPC @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6350.00	Rupees Six Thousand Three Hundred Fifty Only
5	122.85	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint.	Sqm	800.00	Rupees Eight Hundred Only
6	72.80	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1 :2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 ems. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)	m	955.50	Rupees Nine Hundred Fifty Five And Paise Fifty Only



Contractor


Executive Engineer
Project Division
Yelahanka Zone
17/19

Quantity	Item Name	Unit	Rates quoted by Sri.P KRISHNA		
			In figures	In words	
7	175.50	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint.	m	454.10	Rupees Four Hundred Fifty Four And Paise Ten Only
8	132.50	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification.	Sqm	1470.00	Rupees One Thousand Four Hundred Seventy Only
9	32.00	KSRB 14.6 : Providing and laying heavy duty cobble stones interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications 60mm thick	Sqm	1200.00	Rupees One Thousand Two Hundred Only
10	800.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc.,complete.	Nos	454.10	Rupees Four Hundred Fifty Four And Paise Ten Only
11	255.00	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	89.04	Rupees Eighty Nine And Paise Four Only
12	15.00	Providing and fixing polished gray granite slab benches of size 5 ftwidth of seating slab with bottom slab of 75mm thick width 1.50ft with back rest slab of 50 mm thick with 1.50ft depth, side and slab of 100mm thick 2.50 ft height including bull nosing of all edges including fixing in CC 1:2:4 including loading and unloading as per design, specification and fixing as per the directions of the engineer in charge.	Unit	12000.00	Rupees Twelve Thousand Only
13	152.00	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses.	Sqm	159.60	Rupees One Hundred Fifty Nine And Paise Sixty Only
14		GST @ 12%			


Contractor


Executive Engineer
Project Division
Yelahanka Zone